

77 Warren Avenue

Sheet Index:

D-22.01 Cover Sheet

D-22.02 Street Facade and Roof Plan

D-22.03 Sight Line Street Section and Mock-up

D-22.04 Entry Door

D-22.05 Front Windows - Specification

D-22.06 Front Windows - Inventory

D-22.07 Keynotes and Exhibit Photos

D-22.08 Streetscape Photos

D-22.09 Window Specification Exhibit

D-22.10 Window Specification Exhibit

D-22.11 Window Specification Exhibit

D-22.12 Window Specification Exhibit



Sheet: D-22.01

Scope of Work:

A: Mechanical Platform

New roof top condenser units to sit on risers and will be located at the back of the building - adjacent to the private alley at rear of property. The units will sit as low as possible relative to the rubber roof to eliminate visibility from neighboring public streets.

B: New Roof Deck

New wood frame deck with access hatch

C: Window Replacement

All front exterior windows to be replaced with new double hung wood frame windows. Two over two simulated divided lites to resemble building original windows. Interior spacer bars with outside applied muntins on glass face. Finish paint to be dark gray/black similar to neighbor property. Color TBD.

D: Entry Door Replacement

New custom natural finish wood entry door to replace existing non-original door. The intent of re-design and replacement of the front doors is to provide a historically accurate entry door conforming to neighborhood character.

E: Restorations to Building Facade


General repairs and restorations of the building front façade where noted to restore deteriorated architectural elements with new materials and finishes which replicate those of historical examples as closely as possible.






Sheet Index and Project Scope Landmark Review Set

Scale: NA Date: 09.17.19 Project: 77 Warren Ave.








Front Facade, Roof Plan and Mechanical Platform Landmark Review Set

Scale: 3/16"=1'-0"

Date: 09.17.19 Project: 77 Warren Ave.

Sheet: D-22.02



D) SITE SECTION - THROUGH WARREN AVENUE



27 Exhibit - Mock-up roof deck railing - North view



28 Exhibit - Mock-up roof deck railing - North West view

STUDIODYKAS

Street Section Sight Lines and Deck Mock-up


Landmark Review Set


Scale: 1/16"=1'-0" Date: 09.27.19

Project: 77 Warren Ave. Sheet: D-22.03 (REV1)

Note:

studio@studiodykas.com





1 Exhibit - Sample entry doors at neighboring townhouses; 81 and 83 Warren Ave.



2 Exhibit - Sample entry doors at neighboring townhouses; 85 and 87 Warren Ave.




3 Exhibit - Sample entry doors at neighboring townhouses; 93 and 95 Warren Ave.



4 Exhibit - Existing non-original entry door and surround of subject property, 77 Warren Ave.


built.

*With a leaded glass transom and leaded glass door lights, the existing non-compliant door does not resemble a historically accurate door that would have been in place when the property was originally





TYPICAL PROPOSED WINDOW **FULL SECTION** SCALE: 1"=1'-0"



5 Exhibit - Existing non-original window frame and sash of subject property, 77 Warren Ave.

Note: Refer to sheets D-22.09 to D-22.12 for additional manufacturer's info. on windows

STUDIODYKAS

Window Details Landmark Review Set

Scale: As Noted Date: 09.17.19 Project: 77 Warren Ave. Sheet: D-22.05

THIRD FLOOR

SECOND FLOOR

FIRST FLOOR

GARDEN LEVEL



6 Exhibit - Front Facade of subject property with existing windows tagged to reference interior images of same windows on this sheet



7 Exhibit - Existing non-original windows; interior view at Third Filoor



8 Exhibit - Existing non-original windows; interior view at Third Filoor



9 Exhibit - Existing non-original windows; interior view at Garden Filoor



10 Exhibit - Existing non-original windows; interior view at First Filoor

Note: Refer to sheets D-22.09 to D-22.12 for additional manufacturer's info. on windows

STUDIODYKAS

Window Details Landmark Review Set

Scale: As Noted Date: 09.17.19 Project: 77 Warren Ave. Sheet: D-22.06

Work Items - Key Notes

A - Metal Work, Existing

Remove existing non-original metal window boxes, decorative trellis and address plaque. Patch and repair masonry as necessary.

B - Masonry Lintels and Sills, Existing

Repair and paint existing masonry lintels as necessary; to be painted black similar to adjacent townhouse. Color specification to be submitted.

C - Windows

Non-original window frames and sashes to be replaced with new conforming wood frame double hung windows. Two over two simulated divided lites to resemble building original windows. Interior spacer bars with outside applied muntins on glass face. Finish paint to match existing. To be painted black similar to adjacent townhouse. Color specification to be submitted.

D - Entry Vestibule

Remove non-original wood side panels; patch and repair masonry as necessary.

E - Entry Door

Non-original door slab, frame and transom to be replaced with new conforming wood door with two clear lites. To be natural wood with light stain similar to neighboring townhouses. Stain sample specification to be submitted.

F - Wood Awning, Existing

Repair and paint existing wood awning as necessary; to be painted black similar to adjacent townhouse. Color specification to be submitted.

G - Copper Gutter and Downspouts

Install new copper gutters and downspouts to replace existing non-original aluminum items. To match location as existing.

H - Masonry Brick Repair, Existing

Repair and re-point existing brick as necessary. New mortar to match existing.

I - New Mechanical Platform

New wood framed platform on roof to support new condenser units; to be located on roof at height to prevent visibility from public way.

J - New Wood Roof Deck


New wood deck with metal handrail to be located at back of roof to prevent visibility from public way.

K - New Roof Access Hatch

Hinged skylight to provide access to new roof deck.



11 Exhibit - Existing facade of subject property, 77 Warren Ave.



12 Exhibit - Existing non-original entry door and side panels of subject property, 77 Warren Ave.



13 Exhibit - Existing masonry lintel of subject property, 77 Warren Ave.



14 Exhibit - Existing window awning of subject property, 77 Warren Ave.

STUDIODYKAS

Keynotes - General Project Landmark Review Set

Scale: As Noted

Note:

Date: 09.17.19 | Proj

Project: 77 Warren Ave.

Sheet: D-22.07

Subject Property



15 Exhibit - Existing facade of subject property, 77 Warren Ave. with adjacent neighbors.



16 Exhibit - Streetscape; Warren Ave. - view looking East.



17 Exhibit - Streetscape; Warren Ave. - view looking South East across street from subject property



18 Exhibit - Streetscape; Warren Ave. - view looking across street from subject property



19 Exhibit - Streetscape; Warren Ave. - view looking South West across street from subject property

STUDIODYKAS

Existing Conditions and Key Work Items
Landmark Review Set

Scale: As Noted Date: 09.17.19 Project: 77 Warren Ave. Sheet: D-22.08

OMS Ver. 0002.26.00 (Current) Citywide - 77 Warren - Front - 7-12-19 Product availability and pricing subject to change. Citywide - 77 Warren - Front - 7-12-19 Quote Number: C5GNDBY Architectural Project Number: **UNIT SUMMARY** The following is a schedule of the windows and doors for this project. For additional unit details, please see Line Item Additional charges, tax or Terms and Conditions may apply. Detail pricing is per unit. ⊗ Lines with Errors Exist on Project - Unit Pricing is not Valid NUMBER OF LINES: 7 TOTAL UNIT QTY: 20 EXT NET PRICE: USD 15,668.95 LINE MARK UNIT BRAND ITEM NET PRICE QTY **EXTENDED NET** PRICE 1 Garden Level Marvin Wood Ultimate Double Hung RO 35 3/4" X 47 23/32" MO 35 1/4" X 48 3/8" 2 First Floor Wood Ultimate Double Hung RO 35 3/4" X 78 11/32" Entered as MO 35 1/4" X 79" 3 Second Floor Marvin Wood Ultimate Double Hung RO 35 3/4" X 71 23/32" Entered as MO 35 1/4" X 72 3/8" 4 Second Floor Wood Ultimate Double Hung RO 30 1/2" X 71 23/32" Entered as MO 30" X 72 3/8" 5 Third Floor - Front Wood Ultimate Double Hung RO 26 1/8" X 56" Entered as FS 25 1/8" X 55 1/2" ⊗6 Third Floor - Front Wood Ultimate Double Hung RO 48 1/8" X 56" Entered as FS 47 1/8" X 55 1/2" 9 All Wood Windows Marvin Paint the exterior of the windows Black by JB Sash With the High Performance Klima System Accepted: Processed on: 7/12/2019 8:55:14 AM Page 2 of 11

20 Exhibit - New Window Specifications - Marvin Window Quote Page 2

OMS Ver. 0002.26.00 (Current)

STUDIODYKAS

OMS Ver. 0002.26.00 (Current) Citywide - 77 Warren - Front - 7-12-19 Product availability and pricing subject to change Citywide - 77 Warren - Front - 7-12-19 Quote Number: C5GNDBY Architectural Project Number: **LINE ITEM QUOTES** The following is a schedule of the windows and doors for this project. For additional unit details, please see Line Item Quotes. Additional charges, tax or Terms and Conditions may apply. Detail pricing is per unit. Line #1 Mark Unit: Garden Level Net Price: Qty: 2 Ext. Net Price: MARVIN 1 Primed Pine Exterior Painted Interior Finish - White - Pine Interior Wood Ultimate Double Hung Masonry Opening w/ Subsil 35 1/4" X 48 3/8" Rough Opening w/ Subsill 35 3/4" X 47 23/32" Top Sash Primed Pine Sash Exterior WINDOWS: Painted Interior Finish - White - Pine Sash Interior Low E2 w/Argon Black Perimeter and Spacer Bar 7/8" SDL - With Spacer Bar - Black Rectangular - Special Cut 2W1H Primed Pine Ext - Painted Interior Finish - White - Pine Int Ovolo Exterior Glazing Profile Ovolo Interior Glazing Profile **3ottom Sash** As Viewed From The Exterior Primed Pine Sash Exterior Entered As: MO RO 35 3/4" X 47 23/32" Painted Interior Finish - White - Pine Sash Interior Egress Information Width: 31 3/16" Height: 17 23/64" Low E2 w/Argon Black Perimeter and Spacer Bar Net Clear Opening: 3.76 SqFt 7/8" SDL - With Spacer Bar - Black Performance Information U-Factor: 0.29 Rectangular - Special Cut 2W1H Primed Pine Ext - Painted Interior Finish - White - Pine Int Solar Heat Gain Coefficient: 0.26 Ovolo Exterior Glazing Profile Ovolo Interior Glazing Profile Visible Light Transmittance: 0.45 Condensation Resistance: 57 Satin Taupe Sash Lock CPD Number: MAR-N-68-05573-00001 ENERGY STAR: NC White Jamb Hardware Half Screen **Ebony Surround** Charcoal Fiberglass Mesh ***Screen/Combo Ship Loose 4 9/16" Jambs Exterior Casing - None Primed Pine Simulated Thick Subsill No Installation Method ***Note: Screen/Combo/Storm OSM based on factory applied casing and subsill. Field application may require special sizing.


***Note: Unit Availability and Price is Subject to Change Line #2 Mark Unit: First Floor Net Price: Qty: 2 Ext. Net Price: MARVIN-Primed Pine Exterior Painted Interior Finish - White - Pine Interior Built around you Wood Ultimate Double Hung Masonry Opening w/ Subsil Rough Opening w/ Subsil 35 3/4" X 78 11/32" Top Sash Accepted: Processed on: 7/12/2019 8:55:14 AM Page 3 of 11 OMS Ver. 0002.26.00 (Current)

21 Exhibit - New Window Specifications - Marvin Window Quote Page 3

Window Specification Exhibit - Marvin Window Quote, pages 2 and 3
Landmark Review Set


Scale: NA Date: 09.27.19 Project: 77 Warren Ave. Sheet: D-22.09 (REV1)

Note:



22 Exhibit - New Window Specifications - Marvin Window Quote Page 4

STUDIODYKAS




23 Exhibit - New Window Specifications - Marvin Window Quote Page 5


Window Specification Exhibit - Marvin Window Quote, pages 4 and 5
Landmark Review Set

Scale: NA Date: 09.27.19 Project: 77 Warren Ave. Sheet: D-22.10 (REV1)

Note:




24 Exhibit - New Window Specifications - Marvin Window Quote Page 6



25 Exhibit - New Window Specifications - Marvin Window Quote Page 7

> Window Specification Exhibit - Marvin Window Quote, pages 6 and 7 Landmark Review Set Scale: NA Date: 09.27.19 Project: 77 Warren Ave. Sheet: D-22.11 (REV1) Note:



26 Exhibit - New Window Specifications - Marvin Window Quote Page ESDH-21

STUDIODYKAS

Window Specification Exhibit - Marvin Window Quote, page ESDH-21
Landmark Review Set

Scale: NA Date: 09.27.19 Project: 77 Warren Ave. Sheet: D-22.12 (REV1)

Note: