

ITEM 875.13 MULTI-SPACE PARKING METER REMOVE AND RESET EACH

General

This work shall consist of removing and resetting existing multi-space parking meter kiosks as indicated on the Contract drawings or as directed by the Engineer. **Removal of existing multi-space parking meter kiosks will be done by the BTD Operations Division – Meter Shop.** It is the Contractor's responsibility to contact the BTD Operations Division – Meter Shop at least five business days in advance to coordinate the removal of existing multi-space parking meter kiosks. The resetting of multi-space base systems shall be done by the Contractor. A lateral offset of at least 18 inches shall be used.

The multi-space parking meter kiosk must be firmly secured to the sidewalk in accordance with manufacturer's recommendations using a base installation system including all anchors, bolts, plates, foundation (if necessary), etc... approved by BTD Operations Division - Meter Shop. It is the Contractor's responsibility to coordinate this in advance of laying out the multi-space parking meter locations.

The Contractor shall layout new multi-space base system locations and notify BTD Engineering Division - Permits Section at least five (5) business days before the new base system is scheduled to be installed to have a BTD Engineer approve the layout.

The Contractor shall notify the BTD Operations Division - Meter Shop no more than 48 hours after the new base installation system has been installed so BTD can reinstall the multi-space parking meter kiosk unit.

Contact Information

BTB Operations Division – Meter Shop: 617-635-3123 or 617-635-3127

BTB Engineering Division - Permits Section: 617-635-4675

MEASUREMENT AND PAYMENT

Payment for Item 875.13, Multi-Space Meter Remove and Reset, will be at the Contract unit price bid per each. The price and payment will be full compensation for labor, tools, equipment, mounting materials, and all incidental expenses necessary to complete this item to the satisfaction of the Engineer.