

ITEM 877.

SIGN POST REMOVED AND RESET

EACH

Work under this item shall conform to the relevant provisions and amendments of the MassDOT "Standard Specifications for Highways and Bridges", Section 840 and the following:

Sign posts are to be removed and reset where indicated on the plans, unless specifically designated for removal under another item.

Installation of 2-inch steel sign posts shall conform to BTD Standard Plans A201, A203 and A205.

Installation of 2-1/2 inch steel sign posts shall conform to BTD Standard Plan A201.

The Contractor shall unbolt the sign from the post, excavate the post and foundation and remove the concrete foundation from the post. The Contractor shall reattach the sign to the post after the post has been reset. A lateral offset of at least 18 inches shall be used.

Restoration to match adjacent surface will be included in this item when no additional work is proposed in the area of post removal.

In the event that the post is not salvageable, then the Contractor shall furnish a new post, for which payment for the new material will be made as stipulated under the MassDOT "Standard Specifications for Highways and Bridges", Section 840. Posts made non salvageable by the Contractor's careless operations will be replaced by him at no additional cost.

Measurement of sign posts removed and reset will be made by the number each actually removed and reset.

Payment for all work under this item will be made at the contract unit price bid (EACH), which will be full compensation for all labor, tools equipment, material (except new materials required to replace non-salvageable items shall be paid for under other items) and all other incidental expenses necessary to complete the work to the satisfaction of the Engineer.